

Sargent & Lundy EPC Joint Venture with EC Source Services:

- ❑ Public Outreach
- ❑ Engineering and Design / Procurement
- ❑ Construction, Testing and Commissioning

American Electric Power
Texas

The Longview Heights to Marshall Project near Longview, Tex., is being implemented to address potential overload of the existing 69-kV line during outages of interconnecting lines.

The overload issue will be resolved by rebuilding the transmission line from the Longview Heights substation to the Marshall substation.

- Modifications at two substations (Longview Heights and Marshall)
- Rebuilding 18 miles of 69kV line to 138kV
- Distribution underbuild



The execution of this project was performed as a Joint Venture entity called ECSL. Sargent & Lundy is providing the project management, Public Outreach support, procurement, and engineering & design for these projects. EC Source is providing the construction services.

The engineering work began in March 2016. Construction started in October 2016 and complete March 2018.

